

17<sup>th</sup> November, 2020

## Corrigendum


**Subject:- Dismantling and relocation works for proposed NTRI at IIPA, New Delhi.**

While submitting the tender for the subject work on 19.11. 2020, the description of items No. 11, 12, 13 and 24 may be read as provided below in place of description typed in the schedule of quantities provided with the tender on 11<sup>th</sup> November, 2020.

Sl. No.	Description	Qty.	Unit	Rate	Amount
11.	Half brick masonry with common burnt clay FPS (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.  a. Cement mortar 1.3 (1 cement : 3 coarse sand)	200	Sq. Mt.		
12.	Extra for providing and placing in position 2 Nos 6mm dia. M.S. bars at every third course of half brick masonry.	200	Sq. Mt.		
13.	12 mm cement plaster of mix  a. 1.4 (1 cement 4 coarse sand)	150	Sq. Mt.		
24.	Demolishing dry brick pitching in floors, drains etc. Including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	70	Cum		

Rest of the items, quantities and conditions will remain the same.

Inconvenience caused is regretted.

  
(H.O. Goel)  
Executive Engineer